



List of Materials

Item	Description
1	Stainless steel repair clamp, see Section 4-06.02 of these Specifications for approved manufacturer.

Notes:

1. City of Compton street excavation and water permit are required from Public Works Department (first floor of City Hall).
2. Customer must request turn-off and meter removal from Water Utility Division at (310) 605-5690. Water meter must be removed by City 24 hours before water service is to be abandoned or construction begins.
3. Location of corporation stop to be determined by Contractor.
4. Remove abandoned angle meter stop.
5. Water meter box to be removed:
 - a. Parkway - Fill hole with clean dirt and grade level.
 - b. Sidewalk - Sawcut to the closest score mark on each side of meter box and pour sidewalk to meet City Standards.
6. Contractor shall submit to Engineer for approval a notification letter at least 5 working days prior to shutdown. The contractor shall be responsible for dewatering and sending notification letter to all affected users 3 working days prior to outages. The City cannot guarantee a complete water shutdown of existing main. Contractor is responsible for dewatering if necessary. Contractor shall excavate 1 working day in advance of abandonment and plate excavation per Engineer.

REVISED DATE _____ _____ _____ _____	CITY OF COMPTON PUBLIC WORKS DEPARTMENT - WATER UTILITY DIVISION	DRAWN <u>L.H.O.</u> DATE <u>8-25-15</u>
	2" AND SMALLER SERVICE LATERAL ABANDONMENT	STD. NO. <u>646</u>
	APPROVED <u><i>Alvin P...</i></u> DATE <u>9.1.15</u> DIRECTOR OF PUBLIC WORKS AND MUNICIPAL UTILITIES	